

NOTES:
 All notes on this drawing are typical and apply equally to all comparable conditions. Dimensions shall take precedence. Errors or discrepancies on details are to be brought to the attention of the GSDesign Group Inc. before the work or materials have either been commenced, and/or purchased.
 These drawings are the property of the GSDesign Group, Inc. & specifically prepared for the owner of this project at this site and are not to be duplicated or used in part or whole for any other purpose, project location or owner without the express written consent of the GSDesign Group, Inc.



GS Design Group Inc.
 215 Onset Ave.
 P.O. Box 1390
 Onset, MA 02532
 Tel 508 . 295 . 2952

Issued For		
REV.	ISSUE	DATE

LANDSCAPE

Drawing Title:
 Drawn By: Checked By:

L0.0
 Drawing Number:

File Name: Scale: **AS NOTED**
 Date: 7/15/2024

LEGEND		
COMMON NAME	BOTANICAL NAME	QTY
FLOWER, GRASS		
GRASS, 'KARL FOERSTER'	CALAMAGROSTIS X ACUTIFLORA 'KARL FOERSTER'	6
FLOWER, PERENNIAL		
DAYLILY, 'HAPPY RETURNS'	HEMEROCALLIS X 'HAPPY RETURNS'	12
SHRUB, DECIDUOUS		
BLUEBERRY	VACCINIUM CORYMBOSUM SPP.	8
HYDRANGEA, ENDLESS-SUMMER	HYDRANGEA MACROPHYLLA 'ENDLESS SUMMER'	23
HYDRANGEA, INCREDIBALL	HYDRANGEA ARBORESCENS 'ABETWO'	6
HYDRANGEA, LITTLE LAMB TREE	HYDRANGEA PANICULATA 'LITTLE LAMB'	1
SUMMERSWEET, SWEET PEPPERBUSH	CLETHRA ALNIFOLIA 'HUMMINGBIRD'	17
VIBURNUM, AMERICAN CRANBERRYBUSH	VIBURNUM TRILOBUM	14
VIBURNUM, ARROWWOOD	VIBURNUM DENTATUM	22
SHRUB, EVERGREEN BROADLEAF		
HOLLY, JAPANESE	ILEX CRENATA 'STEEDS'	1
INKBERRY, COMPACT	ILEX GLABRA 'COMPACTA'	19
WINTERBERRY	ILEX VERTICILLATA	9
TREE, DECIDUOUS		
AMELANCHIER, ALLEGHENY	AMELANCHIER LAEVIS	7
BIRCH, PAPER OR WHITE	BETULA PAPYRIFERA VAR. COMMUTATA	3
DOGWOOD, KOUSA 4	CORNUS KOUSA	6
HOPHORNBEAM, AMERICAN	OSTRYA VIRGINIANA	4
OAK, WHITE	QUERCUS ALBA	4
REDBUD - EASTERN	CERCIS CANADENSIS	5
TREE, EVERGREEN		
CEDAR, EASTERN RED	JUNIPERUS VIRGINIANA	15
PINE, WHITE	PINUS STROBUS	7

NOTES:
 -LOCATIONS ARE BASED OFF SITE PLAN PROVIDED BY OTHERS
 -ALL MATERIALS TO BE APPROVED BY OWNER
 -ALL UTILITIES TO BE VERIFIED BY DIGSAFE
 -IRRIGATION TO BE INSTALLED TO ALL FINISHED LAWN AREAS AND PLANTING BEDS
 -WELL TO BE INSTALLED FOR IRRIGATION
 -ALL PLANTINGS TO BE INSTALLED BASED ON AMERICAN NURSERYMAN STANDARDS
 -ALL PLANT CAGES AND BALLING/POTTING MATERIAL TO BE REMOVED
 -PLANTING BEDS TO BE PREPARED WITH 50/50 COMPOST AND LOAM WELL MIXED
 -PLANTING BEDS TO BE MULCHED TO A DEPTH OF 2"
 -ALL LAWN AREAS TO BE PREPARED WITH MINIMUM 5" OF SCREENED LOAM
 -DRAIN BASINS TO BE PREPARED AND SEEDED WITH FESCUE BLEND
 -FINISHED LAWN AREAS TO BE HYDRO-SEEDED WITH RYE/BLUEGRASS/FESCUE BLEND
 -WILDFLOWER MIX TO INCLUDE NATIVE POLLINATOR PERENNIALS SUCH AS: ECHINACEA, COREOPSIS, LUPINE ETC.

